

§							
Construction of Boundary Wall, Slab and Misllanious Work in ward no. 15, Gharaunda.							
Sr. No.	Description	Qty.		Rate	Unit	Prem.	Amount
1	2	3		4	5	6	7
1	Excavation/disposal of malba upto 5km lead loading unloading complete in all respect. (HSR item 4.1a+5.2b)	46.57	CUM	141.62	CUM		6595.00
2	Scraping of cement plaster (HSR item- 8.32c)	376.43	Sqm	1.90	Sqm	550%	4649.00
3	Dismantling of old Damage Brick work complete in all respect ( HSR item-8.5 b)	11.67	cum	35.60	cum	550%	2701.00
4	Earth filling upto 5km lead including loading unloading watering and rolling of earth complete in all respect.[HSR ITEM NO. 4.1(a)+5.2(b)]	7.05	cum	141.62	cum		998.00
5	Chowkasts of commercial hard wood such as hillock, champ Cherkassy, and chaplash etc. (Non-coniferous timber other than teak conforming to I.S. specification no. 1003 kiln seasoned) of doors and windows including iron hold fasts, etc., complete fixed in position. (HSR item 17.12)	1.40	CUM	11745.00	CUM	300%	65716.00
6	Factory manufactured panelled door or gla-zed window, shutters of commercial hard wood, such as hollock, champ, chikrassy & chaplash, etc. (non-coniferous timber other than teak, conforming to I.S. specification No. 1003, kiln-seasoned) with 100mm wide vertical styles, 150mm wide lock rail, 200mm wide bottom rail and 100mm wide other rails, with panels of 15mm thick, ton-gued and groovedx of commercial hard wood and including cost of iron hinges, screws, chocks/cleats, stops, nails etc., complete, fixed in position (excluding the cost of any fittings, other than specified above, but including labour for fixing the same in position)-(a)30mm thick[HSR ITEM NO 17.90]	6.50	Sqm	410.00	Sqm	300%	10665.00
7	First class brick work laid in cement sand mortar 1:5. [HSR ITEM NO. 11.3]	26.32	cum	407.60	cum	600%	75093.00
8	Fe-500 EQR TMT steel bars for R.C.C works, where not included in the complete rate of R.C.C. including bending, binding and placing in position complete (HSR 18.22)	650.00	kg	9.17	kg	500%	35763.00
9	12mm thick cement plaster [HSR ITEM NO. 15.5]	305.64	SQM	12.70	sqm	500%	23290.00
10	15mm thick cement plaster[HSR ITEM NO. 15.10]	358.59	SQM	15.65	sqm	500%	33672.00
11	Providing and fixing Vitrified Tiles of size 600x600mm of approved make in flooring laid in any pattern as specified over base of 20 mm thick cement coarse sand mortar 1:3 complete in all respect.[HSR ITEM NO. 14.89]	61.31	SQM	785.65	sqm		48171.00
12	Cement concrete 1:1:5:3 with stone aggregate 20 mm nominal size for reinforced concrete work in slabs with inclination not exceeding 25 degree with horizontal, excluding steel reinforcement, but including centering and shuttering , laid in position, complete in all respects. (HSR item no. 10.82+10.95 a)	8.38	cum	1084.80	cum	450%	50000.00
13	Cement concrete 1 : 8 : 16 with stone aggregate 40 mm Nominal sie in foundation and plinth.[HSR ITEM NO 10.28]	3.25	CUM	318.65	CUM	450%	5696.00
14	Cement concrete 1 : 2 : 4 with stone aggregate 20 mm Nominal sie in foundation and plinth.[HSR ITEM NO 10.41]	2.46	CUM	615.60	CUM	450%	8336.00
15	Providing and applying two coats white cement based putty over plastered surface and grind-ing the surface smooth with sand paper to get an even and smooth finish including coast and carriage of all material, labour charges, scaffolding, suldries etc. Complete.(J.K/Birla Make)[HSR ITEM NO. 16.81]	537.89	SQM	11.35	SQM	230%	20147.00
16	Applying primer coat with Two coats with plastic emulsion paint on wall on new work to give an even shade. [HSR ITEM NO. 16.25+16.30]	282.42	Sqm	14.85	Sqm	230%	13840.00



Sr. No.	Description	Qty.	Rate	Unit	Prem.	Amount
1	2	3	4	5	6	7
	Municipal Engineer		Junior Engineer			
	Municipal Committee Gharunda		Municipal Committee Gharunda			